



**TRAPEZOID
SHAPE 4**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
LEG HEIGHT




**TRIANGLE
SHAPE 6**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT




**OCTAGON
SHAPE 25**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
CONFIRM EACH SIDE
ARE THE SAME




**CIRCLE
SHAPE 51**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
EXACT CIRCLE




**EXACT HALF ROUND
SHAPE 52**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
HEIGHT IS EXACTLY 1/2
OF THE WIDTH




**EXTENDED LEG
SEGMENT
SHAPE 60**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
LEG HEIGHT




**OVAL
SHAPE 61**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
TEMPLATE REQUIRED**




**EXTENDED LEG
HALF ROUND
SHAPE 63**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
ESTIMATED LEG HEIGHT




**HALF ROUND
SHAPE 64**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
ONLY HAS ONE CURVE




**ELLIPSE
SHAPE 65**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
MULTIPLE CURVES
TEMPLATE REQUIRED**



**QUARTER ROUND
SHAPE 67**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
DIMENSION SHOWN AT 45°
(NEED 3 POINTS ON ARC)



**EXTENDED LEG
HALF ROUND
SHAPE 70**

PROVIDE:
OVERALL WIDTH
OVERALL HEIGHT
MIDDLE OF ARC

NOTES:

- 1) ALL DIMENSIONS SHOULD BE TAKEN FROM EDGE OF GLASS, NOT FROM SPACER OR INSIDE OF SPACER.
- 2) PLEASE PROVIDE AND LOCATE AT LEAST THREE POINTS ON ANY ARCS INCLUDED ON SHAPED UNITS.
- 3) ANY GRILLE DIMENSIONS SHOULD BE PROVIDED FROM EDGE OF GLASS TO THE CENTER OF THE GRILLE BEING LOCATED.

Casco Industries, Inc. 5140 Division St. South Elgin, Illinois 60177		SCALE: 1:12	APPROVED BY: <i>KWB</i>	DR.: KWB
		DATE: 08/08/16	GRILLE: -	O.A. DIM: N/A
TOLERANCES UNLESS OTHERWISE SPECIFIED: ONE PLACE .X ±.030 THREE PLACE .XXX ±.005 TWO PLACE .XX ±.015 ANGULAR ±1/2°				
DESCRIPTION: COMMON GLASS SHAPES - REQUESTED DIMENSIONS AND NOTES		DRAWING: GLASSEXP-1		
CUSTOMER: -				